

# Production Report

## SIEMENS

Bid No. 2 - Job No. 1-14-11

Selected Sections: 09900 Painting

Selected Typical Areas:

Selected Areas: (unassigned), FLOOR PLAN

Estimator:

Job Class:

Wage Type: **Open**

Job Status: **PENDING**

Bid Date/Time: **1/14/2011 12:00:00 PM**

Plans Date: **11/25/2010**

### 09900 Painting

#### FLOOR PLAN

Condition Labor Code	Pcs./Hours	Crew Hours	Crew	Installer
1 HM DOOR FRAMES. PTD., 7' 0", 43 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMIGLOSS	1.00 EA	43.00	1.00	DOOR & FRAME PAINTER
2 9'DW WALLS PTD., 9' 0", 17966 SF				
PAINT - Apply Finish Paint, PROGREEN LOW VOC PRIMER	375.00 SF	47.91	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	47.91	1.00	INTERIOR WALLS PAINTER
5 9' ACCENT DW WALLS PTD., 9' 0", 4407 SF 207				
PAINT - Apply Finish Paint, PROGREEN LOW VOC PRIMER	375.00 SF	11.75	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	11.75	1.00	INTERIOR WALLS PAINTER
PAINT - Apply Finish Paint, PROGREEN 200 LOW VOC LATEX EGGSHELL	375.00 SF	11.75	1.00	INTERIOR WALLS PAINTER
6 DBL. HM FRAME, 7", 2 EA				
PAINT - Apply Finish Paint, PROCLASSIC WB ACRYLIC SEMI GLOSS	0.88 EA	2.29	1.00	DOOR & FRAME PAINTER
7 CAULKING PER MH, , 1 EA				
PAINT - Apply Finish Paint	1.00 EA	8.00	1.00	MISCELLANEOUS TRIM PAINTER
8 PATCHING PER MH, , 1 EA				
PAINT - Apply Finish Paint	1.00 EA	8.00	1.00	MISCELLANEOUS TRIM PAINTER